

# LINDEMON WINCKELMANN DEUPREE MARTIN RUSSELL & ASSOCIATES PC

ARCHITECTURE, ENGINEERING & URBAN DESIGN

JAMES N. LINDEMON, RA  
JOHN T. WINCKELMANN, RA  
ALICE LARSEN DEUPREE, RA  
ELI D. MARTIN, RA

PETER KRENICKI, RA  
RONALD J. RUSSELL, RA  
ROBERT SPENCER, PE

## Addenda #2

### RE-BID

ADA Improvements and Other Related Work  
at the  
Old Salem County Courthouse  
for the  
City of Salem  
94 Market Street  
Salem, NJ 08079

January 7, 2009

---

The following items are issued as clarifications, additions, modifications, etc., including items reviewed during the Pre-Bid meeting held at the Old Salem County Courthouse located at 104 Market Street, Salem, NJ at 10:00a.m., on Monday, December 29, 2008. All bidders shall note receipt of this addendum on the proposal form as required and include this information as part of the Project Manual.

**General Note:** Re-bid bid date remains unchanged from **Tuesday, January 20, 2009**, no bids will be accepted after **10:00 a.m.** local time at which time bids will be publicly opened and read aloud.

Items not addressed in Addenda #1 are as follows:

- Item # 1. Please allow \$4.50 per square foot for ceramic floor tile in a 2" x 2" pattern.
- Item # 2. Galvanizing of all new steel members will not be required except where the steel meets stone masonry walls or is below grade.

---

140 BAY STREET, SUITE 4, JERSEY CITY, NJ 07302  
TELEPHONE (201) 333-5017 FAX (201) 333-5309



---

224 NORTH HIGH STREET, MILLVILLE, NJ 08332  
TELEPHONE 856-293-9554 FAX 856-293-1571

mail@lwdmr.com

- Item # 3. Bullet resistant glass is not a part of this bid except at the clerk's window at the rear entry foyer.
- Item # 4. Demolition of the exterior stair to the second floor and the exit door and frame is a part of this bid, as is the new infill masonry at that location.
- Item # 5. The sidewalk pavers existing at the front entry (South side) are to be re-set on a sand base and extended as necessary to create a low ramped sidewalk.
- Item # 6. The ramp at the rear entry (North side) is to be constructed per plans.
- Item # 7. The framing at the new basement and crawl space access panels at the ramp in the courtroom and at the judges / clerks chambers room #110 will be built up from 2' x 6' and 2' x 10' members, sheathed over with ¾" plywood, then final floor finish above (i.e.; original wood in courtroom and carpet in #110).

End  
Addenda #2

